

切盛計画集計表

路線名：カゲ野線

NO. 0～NO. 6+10. 00 L =130. 00m

切盛 1 / 3

作業項目		合計		礫質土	軟岩 I B						m 4	平均距離
総掘削量	CA1	L	324. 95	L	250. 30	L	74. 65					
		C	253. 75	C	187. 72	C	66. 03					
			266. 00		208. 58		57. 42					
総掘削土量変化率		L	1. 2216165									
		C	0. 9539474									
飛散後土量	CA1		266. 00		208. 58		57. 42					
掘削土質率	CA1		1. 0000000		0. 7841353		0. 2158647					
逸散量	CA1		13. 31		10. 44		2. 87					
岩破碎・ブレーカー	CA1		57. 42				57. 42					
流用可能土量	CA1		252. 69		198. 14		54. 55					
津賀の谷作業ポイント	運搬を伴う CA1 (ダンプ)	L	308. 69	L	237. 77	L	70. 92					
			252. 69		198. 14		54. 55				1790680	7086. 47
捨土量合計	運搬を伴う CA1 (ダンプ)	L	308. 69	L	237. 77	L	70. 92					
			252. 69		198. 14		54. 55					
	捨土量合計 CA1	L	308. 69	L	237. 77	L	70. 92					
			252. 69		198. 14		54. 55					
掻均量	津賀の谷作業有	L	308. 69									
			252. 69									
	無	L										
	計	L	308. 69									
			252. 69									
	合計 有	L	308. 69									
			252. 69									
	無	L										
	計	L	308. 69									
			252. 69									

L：ほぐした土量， C：締固め後の土量

切取数量計算表

工種 : CA1

路線名 : カゲ野線

切取 2 / 3

測点名 ＜流用区間距離＞	(修正距離) 単距離	土砂断面積 岩断面積	土砂平均断面積 岩平均断面積	土加減 岩加減	土砂立積 岩立積	飛散量 飛散後立積	逸散量 逸散後立積	現場捨土	＜小計＞ 流用可能立積	礫質土	軟岩 I B					
NO. 0		0.00 0.00														
NO. 1 ＜20.00＞	20.00	0.00 0.00							＜0.00＞							
NO. 2 ＜20.00＞	20.00	0.10 0.00	0.05		1.00	1.00	0.05 0.95		＜0.95＞ 0.95	1.00						
NO. 3 ＜20.00＞	20.00	0.60 0.00	0.35		7.00	7.00	0.35 6.65		＜6.65＞ 6.65	7.00						
NO. 3+15.00	(14.20) 15.00	0.20 0.30	0.40 0.15		5.68 2.13	7.81	0.39 7.42		7.42	5.68	2.13					
NO. 4 ＜20.00＞	(4.40) 5.00	0.70 1.60	0.45 0.95		1.98 4.18	6.16	0.31 5.85		＜13.27＞ 5.85	1.98	4.18					
BC. 4	7.50	1.50 1.90	1.10 1.75		8.25 13.13	21.38	1.07 20.31		20.31	8.25	13.13					
NO. 5 ＜20.00＞	12.50	1.10 1.90	1.30 1.90		16.25 23.75	40.00	2.00 38.00		＜58.31＞ 38.00	16.25	23.75					
EC. 4	5.50	5.30 0.90	3.20 1.40		17.60 7.70	25.30	1.27 24.03		24.03	17.60	7.70					
NO. 6 ＜20.00＞	14.50	7.70 0.00	6.50 0.45		94.25 6.53	100.78	5.04 95.74		＜119.77＞ 95.74	94.25	6.53					
EBC. 5	8.10	4.60 0.00	6.15		49.82	49.82	2.49 47.33		47.33	49.82						
NO. 6+10.00 ＜10.00＞	1.90	2.50 0.00	3.55		6.75	6.75	0.34 6.41		＜53.74＞ 6.41	6.75						
合計	130.00				208.58 57.42	266.00	13.31 252.69		252.69	208.58	57.42					

盛土流用計画表

路線名 : カゲ野線

流用 3 / 3

[illegible]

C: 締固め後の土量