

# 切盛計画集計表

路線名： 令和7年度林業専用道約東田線  
NO. 19～NO. 31 L=240.00m

切盛 1 / 8

作業項目		合計	礫質土	軟岩 I B						m 4	平均距離
総掘削量	CA1	L 4112.32	L 2244.05	L 1868.27							
		C 3335.74	C 1683.04	C 1652.70							
		3307.17	1870.04	1437.13							
総掘削土量変化率		L 1.2434559									
		C 1.0086388									
飛散後土量	CA1	3307.17	1870.04	1437.13							
掘削土質率	CA1	1.0000000	0.5654502	0.4345498							
逸散量	CA1	165.36	93.50	71.86							
岩破碎・ブレーカー	CA1	1437.13		1437.13							
流用可能土量	CA1	3141.81	1776.54	1365.27							
盛土	BS1	L 44.38									
		C 36.00									
		35.69									
	BS2	L 110.52									
		C 89.65									
		88.88									
	BS3	L 305.94									
		C 248.17									
		246.04									
	BT1	L 630.71									
		C 511.60									
		507.22									
	計	L 1091.55									
		C 885.42									
		877.83									
同測点内流用盛土	CA1	L 742.41	L 405.12	L 337.29							
		597.05	337.60	259.45							
工区内運搬盛土	CA1 (ﾀﾝﾌﾟ)	L 349.13	L 190.52	L 158.61							
		280.78	158.77	122.01					7118	25.35	
約東田線作業ポイント	運搬を伴う CA1 (ﾀﾝﾌﾟ)	L 2815.15	L 1536.20	L 1278.95							
		2263.98	1280.17	983.81					398667	176.09	
捨土量合計	運搬を伴う CA1 (ﾀﾝﾌﾟ)	L 2815.15	L 1536.20	L 1278.95							
		2263.98	1280.17	983.81							
	捨土量合計 CA1	L 2815.15	L 1536.20	L 1278.95							
		2263.98	1280.17	983.81							
掻均量	約東田線作業有	L									

L：ほぐした土量， C：締固め後の土量

切盛計画集計表

N0. 19~N0. 31    L = 240. 00m

切盛    2 / 8

作業項目	合計	礫質土	軟岩 IR					m/4	平均距離
------	----	-----	-------	--	--	--	--	-----	------

[illegible][illegible][illegible][illegible]

# 切取数量計算表

工種 : CA1

路線名 : 令和7年度林業専用道約東田線

切取 3 / 8

測点名 〈流用区間距離〉	(修正距離) 単距離	土砂断面積 岩断面積	土砂平均断面積 岩平均断面積	土加減 岩加減	土砂立積 岩立積	飛散量 飛散後立積	逸散量 逸散後立積	現場捨土	〈小計〉 流用可能立積	礫質土	軟岩 I B					
NO. 19		5.80 4.00														
EC. 14	9.50	11.40 0.00	8.60 2.00		81.70 19.00	100.70	5.04 95.66		95.66	81.70	19.00					
NO. 20 〈20.00〉	10.50	1.90 0.00	6.65		69.83	69.83	3.49 66.34		〈162.00〉 66.34	69.83						
NO. 21 〈20.00〉	20.00	6.30 0.00	4.10		82.00	82.00	4.10 77.90		〈77.90〉 77.90	82.00						
NO. 22 〈20.00〉	20.00	15.10 0.00	10.70		214.00	214.00	10.70 203.30		〈203.30〉 203.30	214.00						
NO. 23 〈20.00〉	20.00	10.60 17.70	12.85 8.85		257.00 177.00	434.00	21.70 412.30		〈412.30〉 412.30	257.00	177.00					
NO. 24 〈20.00〉	20.00	3.90 18.40	7.25 18.05		145.00 361.00	506.00	25.30 480.70		〈480.70〉 480.70	145.00	361.00					
NO. 25 〈20.00〉	20.00	11.10 8.50	7.50 13.45		150.00 269.00	419.00	20.95 398.05		〈398.05〉 398.05	150.00	269.00					
NO. 26 〈20.00〉	20.00	2.40 9.50	6.75 9.00		135.00 180.00	315.00	15.75 299.25		〈299.25〉 299.25	135.00	180.00					
NO. 27 〈20.00〉	20.00	4.10 5.60	3.25 7.55		65.00 151.00	216.00	10.80 205.20		〈205.20〉 205.20	65.00	151.00					
MC. 20 9.25		7.90 3.70	6.00 4.65		55.50 43.01	98.51	4.93 93.58		93.58	55.50	43.01					
NO. 28 〈20.00〉	10.75	11.70 10.30	9.80 7.00		105.35 75.25	180.60	9.03 171.57		〈265.15〉 171.57	105.35	75.25					
NO. 29 〈20.00〉	20.00	5.50 2.90	8.60 6.60		172.00 132.00	304.00	15.20 288.80		〈288.80〉 288.80	172.00	132.00					
NO. 30 〈20.00〉	(20.60) 20.00	11.20 0.00	8.35 1.45		172.01 29.87	201.88	10.09 191.79		〈191.79〉 191.79	172.01	29.87					
NO. 30+10.00 10.00	(10.15) 10.00	10.80 0.00	11.00		111.65	111.65	5.58 106.07		106.07	111.65						
NO. 31 〈20.00〉	10.00	0.00 0.00	5.40		54.00	54.00	2.70 51.30		〈157.37〉 51.30	54.00						
合計	240.00				1870.04 1437.13	3307.17	165.36 3141.81		3141.81	1870.04	1437.13					

盛土数量計算表

路線名：令和7年度林業専用道約束田線

盛土 4 / 8

測点名 〈流用区間距離〉	単距離	BS1					BS2					BS3				
		修正距離	断面積	平均	加減	立積	修正距離	断面積	平均	加減	立積	修正距離	断面積	平均	加減	立積
NO. 19			0.00					0.00					0.00			
EC. 14	9.50		0.00					0.00					0.00			
NO. 20 〈20.00〉	10.50		0.00			<0.00>		2.60	1.30		<13.65> 13.65		0.00			<0.00>
NO. 21 〈20.00〉	20.00		0.00			<0.00>		2.50	2.55		<51.00> 51.00		0.00			<0.00>
NO. 22 〈20.00〉	20.00		0.00			<0.00>		0.00	1.25		<25.00> 25.00		0.00			<0.00>
NO. 23 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		0.00			<0.00>
NO. 24 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		0.00			<0.00>
NO. 25 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		0.00			<0.00>
NO. 26 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		0.00			<0.00>
NO. 27 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		1.00	0.50		<10.00> 10.00
MC. 20	9.25		0.00					0.00					0.90	0.95		8.79
NO. 28 〈20.00〉	10.75		0.00			<0.00>		0.00			<0.00>		0.00	0.45		<13.63> 4.84
NO. 29 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>		1.70	0.85		<17.00> 17.00
NO. 30 〈20.00〉	20.00		0.00			<0.00>		0.00			<0.00>	16.25	14.75	8.23		<133.74> 133.74
NO. 30+10.00	10.00		0.00					0.00					0.00	7.38		73.80
NO. 31 〈20.00〉	10.00		7.20	3.60		<36.00> 36.00		0.00			<0.00>		0.00			<73.80>
合計	240.00					36.00					89.65					248.17



## 盛土流用計画表

路線名 : 令和7年度林業専用道約束田線

流用 6 / 8

[illegible]

C: 締固め後の土量

### 構造物数量計算表

路線名： 令和7年度林業専用道約束田線

構造 7 / 8

測点名	単距離	切土法面											
		修正距離	断面	平均	数量								
NO. 19			2. 90										
EC. 14	9. 50		5. 10	4. 00	38. 00								
NO. 20	10. 50		0. 80	2. 95	30. 98								
NO. 21	20. 00		3. 00	1. 90	38. 00								
NO. 22	20. 00		4. 10	3. 55	71. 00								
NO. 23	20. 00		3. 40	3. 75	75. 00								
NO. 24	20. 00		2. 60	3. 00	60. 00								
NO. 25	20. 00		5. 40	4. 00	80. 00								
NO. 26	20. 00		0. 80	3. 10	62. 00								
NO. 27	20. 00		0. 70	0. 75	15. 00								
MC. 20	9. 25		3. 70	2. 20	20. 35								
NO. 28	10. 75		5. 70	4. 70	50. 53								
NO. 29	20. 00		3. 50	4. 60	92. 00								
NO. 30	20. 00		4. 60	4. 05	81. 00								
NO. 30+10. 00	10. 00			2. 30	23. 00								
NO. 31	10. 00												
合計	240. 00				736. 86								

### 構造物数量集計表

路線名：令和7年度林業専用道約束田線

N0. 19~N0. 31    L=240.00m

構集 8 / 8

[illegible]