

切盛計画集計表

路線名：柳野カゲ線1号箇所
+0.00～+14.50 L=14.50m

切盛 1 / 5

| 作業項目 | | 合計 | | 礫質土 | 礫質ルース | | | | | | m 4 | 平均距離 |
|----------|----------|----|-----------|-----|-----------|---|-----------|--|--|--|--------|----------|
| 総掘削量 | CA2 | L | 16.14 | L | 15.89 | L | 0.25 | | | | | |
| | | C | 12.11 | C | 11.92 | C | 0.19 | | | | | |
| | | | 13.45 | | 13.24 | | 0.21 | | | | | |
| | CA5 | L | 23.15 | | | L | 23.15 | | | | | |
| | | C | 17.36 | | | C | 17.36 | | | | | |
| | | | 19.29 | | | | 19.29 | | | | | |
| | 計 | L | 39.29 | L | 15.89 | L | 23.40 | | | | | |
| | | C | 29.47 | C | 11.92 | C | 17.55 | | | | | |
| | | | 32.74 | | 13.24 | | 19.50 | | | | | |
| 総掘削土量変化率 | | L | 1.2000611 | | | | | | | | | |
| | | C | 0.9001222 | | | | | | | | | |
| 飛散後土量 | CA2 | | 13.45 | | 13.24 | | 0.21 | | | | | |
| | CA5 | | 19.29 | | | | 19.29 | | | | | |
| | 計 | | 32.74 | | 13.24 | | 19.50 | | | | | |
| 掘削土質率 | CA2 | | 1.0000000 | | 0.9843866 | | 0.0156134 | | | | | |
| | CA5 | | 1.0000000 | | | | 1.0000000 | | | | | |
| | 計 | | 1.0000000 | | 0.4043983 | | 0.5956017 | | | | | |
| 流用可能土量 | CA2 | | 13.45 | | 13.24 | | 0.21 | | | | | |
| | CA5 | | 19.29 | | | | 19.29 | | | | | |
| | 計 | | 32.74 | | 13.24 | | 19.50 | | | | | |
| 捨土場所1 | 運搬を伴う | | | | | | | | | | | |
| | CA2(ダンプ) | L | 16.14 | L | 15.89 | L | 0.25 | | | | | |
| | | | 13.45 | | 13.24 | | 0.21 | | | | 176195 | 13100.00 |
| | CA5(ダンプ) | L | 23.15 | | | L | 23.15 | | | | | |
| | | | 19.29 | | | | 19.29 | | | | 252699 | 13100.00 |
| | 計 | L | 39.29 | L | 15.89 | L | 23.40 | | | | | |
| | | | 32.74 | | 13.24 | | 19.50 | | | | 428894 | 13100.00 |
| 捨土量合計 | 運搬を伴う | | | | | | | | | | | |
| | CA2(ダンプ) | L | 16.14 | L | 15.89 | L | 0.25 | | | | | |
| | | | 13.45 | | 13.24 | | 0.21 | | | | | |
| | CA5(ダンプ) | L | 23.15 | | | L | 23.15 | | | | | |
| | | | 19.29 | | | | 19.29 | | | | | |
| | 計 | L | 39.29 | L | 15.89 | L | 23.40 | | | | | |
| | | | 32.74 | | 13.24 | | 19.50 | | | | | |
| | 捨土量合計 | | | | | | | | | | | |
| | CA2 | L | 16.14 | L | 15.89 | L | 0.25 | | | | | |
| | | | 13.45 | | 13.24 | | 0.21 | | | | | |
| | CA5 | L | 23.15 | | | L | 23.15 | | | | | |
| | | | 19.29 | | | | 19.29 | | | | | |
| | 計 | L | 39.29 | L | 15.89 | L | 23.40 | | | | | |
| | | | | | | | | | | | | |

L：ほぐした土量， C：締固め後の土量

[illegible]

L : ぼぐした土量, C : 締固め後の土量

切取数量計算表

工種 : CA2

路線名 : 柳野カゲ線1号箇所

切取 3 / 5

| 測点名 ＜流用区間距離＞ | (修正距離) 単距離 | 土砂断面積 岩断面積 | 土砂平均断面積 岩平均断面積 | 土加減 岩加減 | 土砂立積 岩立積 | 飛散量 飛散後立積 | 逸散量 逸散後立積 | 現場捨土 | ＜小計＞ 流用可能立積 | 礫質土 | 礫質ノース | | | | | |
|-------------------|----------------|---------------|-------------------|------------|-------------|--------------|--------------|------|-----------------|-------|-------|--|--|--|--|--|
| +0.00 | | 0.00 | | | | | | | | | | | | | | |
| +1.50 | (0.85) 1.50 | 3.30 | 1.65 | | 1.40 | 1.40 | 1.40 | | 1.40 | 1.27 | 0.13 | | | | | |
| +6.50 | (0.55) 5.00 | 3.80 | 3.55 | 0.80 | 2.75 | 2.75 | 2.75 | | 2.75 | 2.67 | 0.08 | | | | | |
| +11.90 | (0.75) 5.40 | 4.70 | 4.25 | | 3.19 | 3.19 | 3.19 | | 3.19 | 3.19 | | | | | | |
| +14.50 ＜14.50＞ | 2.60 | 0.00 | 2.35 | | 6.11 | 6.11 | 6.11 | | ＜13.45＞ 6.11 | 6.11 | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| 合計 | 14.50 | | | 0.80 | 13.45 | 13.45 | 13.45 | | 13.45 | 13.24 | 0.21 | | | | | |

| 切取数量計算表 | | | | | | | | | | | | | | | |
|-------------------|----------------|-----------------|-------------------|------------|-------------|--------------|--------------|------|-----------------|-----|--------|----------|--|--|--|
| 工種　：　CA5 | | 路線名　：　柳野カグ線1号箇所 | | | | | | | | | | 切取　4　/　5 | | | |
| 測点名 ＜流用区間距離＞ | (修正距離) 単距離 | 土砂断面積 岩断面積 | 土砂平均断面積 岩平均断面積 | 土加減 岩加減 | 土砂立積 岩立積 | 飛散量 飛散後立積 | 逸散量 逸散後立積 | 現場捨土 | ＜小計＞ 流用可能立積 | 礫質土 | 礫質ルース* | | | | |
| +0.00 | | 0.00 | | | | | | | | | | | | | |
| +1.50 | (1.25) 1.50 | 2.70 | 1.35 | | 1.69 | 1.69 | 1.69 | | 1.69 | | 1.69 | | | | |
| +6.50 | (3.35) 5.00 | 1.50 | 2.10 | | 7.04 | 7.04 | 7.04 | | 7.04 | | 7.04 | | | | |
| +11.90 | (3.50) 5.40 | 2.60 | 2.05 | | 7.18 | 7.18 | 7.18 | | 7.18 | | 7.18 | | | | |
| +14.50 ＜14.50＞ | 2.60 | 0.00 | 1.30 | | 3.38 | 3.38 | 3.38 | | ＜19.29＞ 3.38 | | 3.38 | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| 合計 | 14.50 | | | | 19.29 | 19.29 | 19.29 | | 19.29 | | 19.29 | | | | |

盛土流用計画表

路線名 : 柳野カゲ線1号箇所

流用 5 / 5

[illegible]

C: 締固め後の土量